

FLOOR PLAN

SCALE: 3/16" = 1'-0"


NOTES

- (A) 3'-0" X 7'-0" DR. & WND. BRONZE ALUMINUM STOREFRONT ASSY. (R.O. 54-1/2" X 86-1/2")
- (B) 3'-0" X 7'-0" EXTER. STL. DRS. W/MTL. FRAMES & PANIC HARDWARE (R.O. 40-1/4" X 86")
- (C) 3'-0" X 7'-0" SOLID CORE WD. DRS. W/ MTL. FRAMES (R.O. 38" X 85") W/PASSAGE SET (DR. OFC. TO HAVE KEYED LOCK & R.R. TO HAVE PRIVACY SET)
- (D) 3'-0" X 7'-0" SOLID CORE WD. DRS. W/ MTL. FRAMES & LEVER HANDLES (R.O. 38" X 85") (R.R. TO HAVE PRIVACY SET)
- (E) 3'-0" X 7'-0" SOLID CORE WD. DRS. W/ MTL. FRAMES (R.O. 38" X 85") W/KEYED LOCK & TACTICAL WARNING KNOB
- (F) DBL. 3'-0" X 7'-0" SOLID CORE WD. DRS. W/ MTL. FRAMES (R.O. 74" X 88") W/KEYED LOCK & TACTICAL WARNING KNOB
- (G) 4'-0" X 7'-0" SOLID CORE WD. DRS. W/ MTL. FRAMES (R.O. 50" X 85") W/PASSAGE SET
- (H) 4'-0" X 7'-0" EXTER. STL. DRS. W/MTL. FRAMES & PANIC HARDWARE (R.O. 52-1/4" X 86")
- (I) WINDOWS TO BE 2'-0" X 5'-3" BRONZE ALUM. FIXED (R.O. 24" X 63" UP 21")
- (2) WINDOWS TO BE 2'-6" X 5'-3" BRONZE ALUM. FIXED (R.O. 30" X 63" UP 21")
- (3) WINDOWS TO BE 4'-6" X 7'-0" BRONZE ALUM. FIXED/SAFETY GLAZED (R.O. 54" X 104" UP 6'11")

REVISIONS:

6-24-94
4-27-95

THE DATA FURNISHED IN THESE DRAWINGS ARE IN RESPONSE TO A REQUEST FOR PROPOSAL TO DESIGN AND CONSTRUCT A MEDICAL BUILDING. THE DRAWINGS SHALL NOT BE DISCLOSED OR REPRODUCED IN WHOLE OR IN PART FOR ANY PURPOSE OTHER THAN THAT EVALUATED TO THIS OFFEROR AS RESULT OF OR IN CONNECTION WITH THE SUBMITTAL OF THIS OFFER. THE OFFEROR SHALL HAVE NO LIABILITY TO THE CLIENT OR ANY OTHER PARTY TO THE CONTRACT.



4/21/94

RMD
Manufacturing, Ltd.
1402 U.S. HWY. 287 SOUTH
MANFORD, TEXAS 76865

FOR: **RAMTECH BUILDING SYSTEMS, INC.**
PROJECT: **JACKSON COUNTY MEDICAL CLINIC**
EDNA, TEXAS

DATE: 6-17-94

DRAWN BY: DMV

CHECKED BY:

SHEET NO. 2 OF 9

A7B.1

"AS - BUILT" DRAWING